

Lessons Learned from Large-scale Wetland Design, Construction and Operation

November 2002

**Gary Goforth, P.E., Ph.D.
Chief Consulting Engineer**

South Florida Water Management District





Overview

- ◆ Everglades Construction Project
- ◆ Lessons learned
 - Planning
 - Design
 - Construction
 - Operation



You are here



Everglades






Everglades Restoration

- ◆ 4 major problems facing Everglades ecosystem:
 - Reduction in spatial extent of wetlands
 - Degradation of water quality (e.g., phosphorus and mercury)
 - Disruption of hydroperiods (i.e., timing, volume & distribution)
 - Infestation by exotic plant species
- ◆ ECP designed to address first 3



Everglades Construction Project

- ◆ Six large constructed wetlands
 - 870 acres to over 16,600 acres
 - 10-yr \$700 million construction
 - “Passive” biological treatment - yet over 250 control structures, 150 miles of canals/levees
 - combination of emergent, SAV and existing wetland vegetation
 - four are complete; 2 under construction
- ◆ Critical for Everglades restoration
 - reduce phosphorus to 50 ppb and lower
 - increase quantity of inflows
 - improve distribution of inflows






40,000 of prior agriculture lands




5,000 acres of remnant Everglades habitat



Everglades Nutrient Removal Project - 3,800-ac demonstration project






Cell 1 - self organizing vegetation communities







STA-5 - start-up

Cell 1B

Cell 1A



STA-6





STA Sizing

STA	Flow AF/yr	Load MT/yr	Size ha
STA 1E	124,876	29.4	2,170
STA 1W	142,860	37.7	2,700
STA 2	174,641	33.7	2,600
STA-3/4	604,655	87.3	6,745
STA 5	78,340	25.3	1,670
STA 6	53,877	13.2	960



STA Summary

- ◆ 6 large constructed wetlands totaling over 19,300 ha to treat 331,174 ha of tributaries (6%)
- ◆ ~1,180,000 AF/yr & ~227 MT/yr
- ◆ Goal is 50 ppb outflow; ~164 MT/yr removal
- ◆ Peat soils that vary in organic content
- ◆ Surface flow wetland treatment systems
- ◆ Long-term P removal through peat accretion
- ◆ Utilizing a combination of existing wetland plants, volunteer recruitment, and management to encourage submerged aquatic vegetation/algal communities
- ◆ Performance to date has exceeded expectations!



Lessons Learned

- ◆ Still writing the book
- ◆ Have spent hundreds of hours compiling lessons learned
- ◆ Will highlight significant lessons learned to date



Planning

- ◆ Establish effective teams
 - internal: scientists and engineers
 - external: agencies, stakeholders and technical experts
- ◆ Establish clear project targets
- ◆ Characterize hydrologic and nutrient inputs
- ◆ Identify and evaluate alternatives
- ◆ Retool business practices



Design - Process

- ◆ STA Design review group began 1991
- ◆ Utilized combination of consultants and in-house design
- ◆ Continual exchange of ideas between team members – scientists and engineers, etc.
- ◆ Site manager and operations staff active during design
- ◆ Extensive peer-review
- ◆ Creative land management - long-term plan




Design - details

- ◆ Good topographic surveys are critical
- ◆ Know what the desired vegetation type will be - design for min./max. and average operating depths
- ◆ Vegetation barriers necessary at all structures
- ◆ Consider prior land use
- ◆ Understand nutrient dynamics
- ◆ Utilize depth-dependent variable Manning's "n" for modeling flows



Influence of depth on Manning's "n" for a cattail marsh





Design - details (cont'd)

- ◆ use of standard designs – structures, levees, etc.
 - passive split level gates to maintain operating depths
- ◆ consider monitoring equipment, structure calibration, flow monitoring during design
- ◆ prepare water management and dewatering plans prior to construction – keep water onsite to accelerate growth of wetland vegetation
- ◆ can never have too much geotechnical data – minimize contractor claims
- ◆ automated trash racks for pump stations



Design - concluded

- ◆ Performance related to hydraulic efficiency
 - minimize short circuiting
 - plug field ditches parallel to flow
 - leave transverse canals for redistribution
 - use spreader canals, collection canals
 - compartmentalization - hydraulic redistribution
- ◆ Seepage can be significant
- ◆ *Consider new information during design*



Permitting

- ◆ *Meet early and often with regulatory agencies; educate the regulator*
- ◆ Plan resources for permit administration and acquisition
- ◆ Permit conditions should allow for operational flexibility
- ◆ Minimize monitoring requirements – long-term financial obligation and most data are not reviewed by regulatory agencies
- ◆ Streamline reporting requirements to minimize resource commitments



Construction

- ◆ Hold mandatory pre-bid conferences
- ◆ Minimize number of different prime contractors
- ◆ Formal partnering agreements/kick-off meetings prior to construction for addressing problems
- ◆ Site manager active during construction
- ◆ Vegetation management plans



Operations

- ◆ *Communication, communication, communication!*
- ◆ Keep the team together – monitor operations frequently
- ◆ Commit the staff and \$ resources required
- ◆ Develop operation plan (construction, start-up and normal ops) early and obtain broad review
- ◆ Review operation plan frequently – every 6-12 months; document deviations immediately for posterity



Operations - cont'd

- ◆ Large-scale systems are self-designing – contingency plans
- ◆ Flush submerged aquatic vegetation periodically to avoid major build up and pump shut down
- ◆ Stay ahead of (i.e., herbicide) undesirable vegetation – early and appropriate periodicity
- ◆ Annual aerial photos are very beneficial



Operations - concluded

- ◆ Continue monitoring/researching ways to improve/optimize performance
- ◆ Performance – frequent review and analysis to catch and correct problems as soon as possible; run models frequently with actual data
- ◆ Communication, communication, communication!



For More Information:

- ◆ www.sfwmd.gov
 - Major Projects
 - Everglades Restoration
 - Everglades Construction Project

- ◆ Everglades Consolidated Report
 - Summary of all available data
 - <http://www.sfwmd.gov/org/ema/everglades/index.html>

- ◆ Gary Goforth (561) 682-6280
 - ggoforth@sfwmd.gov